

# TIKI DRIVE ROAD RENOVATION

## BORA BORA TO ISLES END

### ADDENDUM #1

NOVEMBER 22, 2016

- **RAIN DELAYS-** Rain delays will be determined by the National Weather Service in Galveston as well as the Mayor of Tiki Island.
- **LABORATORY TESTING SERVICES-** The Contractor will **not** be responsible for providing laboratory testing. Laboratory testing will be provided by the Village of Tiki Island.
- **2" SAND BASE REQUIREMENT-** The requirement of the 2" sand base is removed and will not need to be bid.
- **ALTERNATE BID REQUEST-** An alternate bid is requested for 8" at 6% compaction lime stabilization.
- **DRIVEWAY RADIUS-** Please see attached drawing for alternate driveway approach.
- **CONCRETE LOADS** 10 yard loads of concrete will be permitted for this project.
- **BRIDGE WEIGHT LIMITS-** Bridge weight limits will be lifted for this project. In some cases it will be determined if the equipment can be walked across the bridge in the interest of preserving load limits.
- **STAGING AREAS-** Staging areas, Wash Out areas, and Water supply areas will be determined and discussed with the winning bidder. Water will be provided by G.C.F.W.S.D. #6 but must be metered.

**All Proposals turned in will be per plans, specs and Addendums, with no exceptions made.**